



*SC Magnets
at Fermilab*

Small Racetrack – Design, Mechanical Analysis and Fabrication

Srinivas Bhashyam



SC Magnets
at Fermilab

Outline

❖ **Design Overview**

- **Mechanical Structure**
- **Winding Assembly**
- **Tooling**

❖ **Magnetic/Mechanical Analysis Summary**

- **Design Criteria**
- **Shell Stresses/Strains**
- **Coil Stresses/Displacements**

❖ **Fabrication**

- **Procurement Status**
- **Fabrication scenarios and schedule**



SC Magnets
at Fermilab

Design Overview

❖ **Mechanical Structure**

- **Yoke, skin, pressure pad, keys – identical to LBL design**
- **Steel skin thickness – scaled to 3.99 mm (LBL design 1.35 mm) to compensate for difference in thickness of coil package – FNAL single coil package, LBL two coil package**
- **End support parts – scaled to FNAL cable width**

❖ **Winding Assembly**

- **Wider cable – FNAL $\cos(\theta)$ cable**
- **Double layer design (no interlayer splice) – 13 turns**
- **Modified pole piece**
- **Horseshoe, end shoe scaled to FNAL cable width**
- **Leads on the same side**



❖ **Tooling**

- **Reaction, impregnation tooling parts scaled to FNAL cable width (where appropriate)**



SC Magnets
at Fermilab

Design Overview – Mechanical Structure




End supports – 304 Steel




SC Magnets
at Fermilab

Design Overview – Winding Assembly



13 turns




R = 18.6 mm

R = 17.3 mm




*SC Magnets
at Fermilab*

Design Overview – Tooling



Reaction Fixture




Impregnation Fixture



SC Magnets
at Fermilab

Magnetic Analysis






All parts in purple represent iron – saturation effects included



SC Magnets
at Fermilab

Magnetic Analysis

$I = 28 \text{ kA}$



- Peak field = 10.7 T
- Total coil separation force ↗ 850 kN
- Peak field based on roxie = 11.2 T, coil separation force = 750 kN
(Vadim Kashikin)




SC Magnets
at Fermilab

Mechanical Analysis – Design Criteria and Specifications

- ❖ **No coil separation allowed @ $I_{\max} = 28$ kA (Reacted Nb₃Sn cable in the transition region from the top layer to the bottom layer)**
 - ❧ **Coil remains under compression @ 4.2 K, $I_{\max} = 28$ kA**
- ❖ **Maximum shell stress during bladder operation < yield stress of 6061 T6 Aluminum = 250 MPa**
- ❖ **Maximum coil stresses during assembly and cool-down < 150 MPa**
- ❖ **Key/yoke interference = 0.5 mm**
- ❖ **Bladder pressure required for inserting keys = 60 MPa**
- ❖ **Minimum friction between yoke and skin to reduce shell stresses during bladder operation**
- ❖ **Shell stresses monitored using strain gages**

Mechanical Analysis – ANSYS Model and Material Properties







Material	Modulus (GPa)		Poisson's Ratio	Integrated Thermal Contraction (mm/m)
	4.2 K	300 K		
6061 Aluminum	80	70	0.3	4.35
1018 Steel	225	210	0.3	2.07
304 Steel	225	210	0.3	3.02
Coil	35	35	0.3	3.58
G-10	14	14	0.3	7.62

- Surface-surface contact elements ($\mu = 0.15$)
- $\mu = 0$ contact elements between shell and yoke



SC Magnets
at Fermilab





Mechanical Analysis – Azimuthal Shell Stresses





SC Magnets
at Fermilab

Mechanical Analysis – Azimuthal Shell Strains






SC Magnets
at Fermilab


Mechanical Analysis – Radial (S_x) Coil

Stresses


Bladder on @ 60 MPa




Bladder off, keys on



4.2 K



4.2 K, 28 kA







SC Magnets
at Fermilab

Mechanical Analysis – Radial (U_x) Coil Displacements


Bladder off, keys on



4.2 K



4.2 K, 28 kA





SC Magnets
at Fermilab

Fabrication – Procurement Status

Description	Design Modifications/ Drawings Release	Procurement	Expected Final Delivery Date	No. of sets
coil winding assembly	completed	Parts in QC	Aug 15,2003	2
mechanical structure	completed	Parts in QC	Aug 15,2003	2
Tooling – Reaction/Impregnation	completed	Requisition initiated	Sept 15 ,2003	2



*SC Magnets
at Fermilab*

Fabrication – Schedule



*SC Magnets
at Fermilab*

Fabrication – Schedule



*SC Magnets
at Fermilab*

Summary

- ❖ **Design changes have been kept to a minimum**
- ❖ **Modifications are being validated using FEA**
- ❖ **Fabrication process has to follow LBL procedures as closely as possible (including the subtle steps)**
- ❖ **Strong collaboration between FNAL and LBL essential for successful execution of the first small racetrack model magnet**